7. The full value of all timber purchased shall be paid for within 30 days after the date of sale or within 15 days after the date of the notice of confirmation of the sale, whichever is later. In case of purchasers of above Rs. 1,000 in value, the purchaser shall be permitted to pay up the balance in instalments of not less than Rs. 1,000, provided the full value is paid not later than the 20th June 1928. The moneys shall be paid into such treasury as the District Forest Officer may direct, within the time specified.

8. If the amount is not fully paid for by the purchaser before the dates fixed above, the initial deposit as well as the other moneys already paid in shall be forfeited to Government and all or any portion of the timber not fully paid for shall be resold at the risk of the purchaser in the manner prescribed for default of payment of one-tenth value in clause 5 *supra*.

9. No timber lot shall be permitted to be removed by the purchaser unless it has been paid for in full, calculated at the rates at which the timber is knocked down to him at the time of sale, excluding the 10 per cent deposit paid for the lot at the time of the sale; and no timber shall be removed from the depot unless a permit is obtained from the Forest Officer in charge of the depot. The earnest money will not be adjusted towards the value of timber, until 90 per cent of the purchase money over and above the security deposit has been paid.

10. Timber purchased should be removed as early as possible, and in no case should it be allowed to remain longer than 90 days after the dates fixed in clause 7 *supra*. Timber not removed after purchase, will remain in the depot at the risk of the purchaser from the date of the confirmation of the sale.

11. If the timber is not removed within the time allowed, the same may, after ten days' notice to the purchaser, be sold in public auction and the proceeds will be given to the purchaser after defraying all the expenses in connection with the resale.

12. The deposit of Rs. 200 will remain as security for the due fulfilment of all and every one of the terms of sale, on the breach of any of which by the purchaser, the District Forest Officer shall be entitled to forfeit the deposit in whole or in part and in the event of such forfeiture, the sum so forfeited shall be immediately made good by the purchaser so long as the transaction is not finally closed. The security deposit or the balance thereof, if any, shall be returned to the purchaser after the full value of timber purchased has been paid for and the timber fully removed.

M. V. NARASIMHAIYA,
District Forest Officer.

ENGINEERING DEPARTMENT.

BANGALORE DIVISION.

Notice dated 29th December 1927.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M., on 16th January 1928, for the construction of a combined building for the Sub-Registrar's Offices and Bonded Depot at Nelamangala. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rupees two hundred and fifty in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Constructing a building for the Sub-Registrar's Office and Bonded Depot at Nelamangala, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

sted on the notice board in the Executive Engineer's Office in due course. No enquiries garding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be urned.

Abstract of quantities for constructing Sub-Registrar's Office and Bonded Depot at Nelamangala.

No.	Items of work	Per	Quantity	Rate
1	Earthwork excavation	Cyds.	123	
2	Burnt stone jelley in lime mortar concrete ...	C.ft.	672	
3	Burnt stone in clay	,,	2,730	
4	Burnt brick in clay	,,	2,789	
5	Burnt brick in lime mortar	,,	673	
6	Teakwood battened door 1¼" thick shutter including all iron fittings, etc.	S.ft.	137	
7	Teakwood battened door 1¼" thick plank iron fittings with four leaves.	,,	45	
8	Teakwood battened windows 1" thick with ¾" iron bars and all iron fittings.	,,	268	
9	Teakwood glazed ventilators with iron bars, etc., complete.	,,	11	
10	Teakwood work wrought and put up with wood-oiling	C.ft.	78·30	
11	Steel joists including hoisting	Cwt.	35·00	
12	Stone wall plate 4" × 6"	R.ft.	96	
13	Jack arch roofing complete	Sqr.	6·34	
14	Roofing with First Class Mangalore tiles on teak reepers complete.	,,	19·14	
15	Ridge tiles set in mortar	R.ft.	53	
16	Dressed stone pillars for verandah with iron clamps etc.	Each	14	
17	Burnt stone slabs 6" roughly dressed	S.ft.	500	
18	Cornice 9" thick	R.ft.	225	
19	Parapet wall 2' high brick in clay and chunam plastered	,,	118	
20	Flooring with Caddapah slab 1½" thick on 3" concrete bed and cement pointing.	Sqr.	14·76	
21	Teakwood eave board	R.ft.	160	
22	Teakwood finials	Each	2	
23	Teakwood pendents	,,	6	
24	Binding wall over gable	R.ft.	40	
25	Plastering with mortar	Sqr.	67·40	
26	Tarring to wood work	,,	5·00	
27	Chacolate painting	,,	14·60	
28	Cement pointing	,,	2·34	
29	White and colour washing	,,	67·40	
30	Partition between store room and top with iron bars flat iron and angle iron work, complete.	S.ft.	120	

R. W. SCALDWELL,
Executive Engineer.

KOLAR DIVISION.

Dated 17th December 1927.

Notice is hereby given that sealed tenders will be received at the Office of the Executive gineer, Kolar Division, up to 2 P.M., on 25th January 1928, for restoring Belamaranahalli elinakere Major Tank, R. No. 258 of Kolar Taluk. An approximate estimate of quantities given below. These quantities are not guaranteed. The work should be completed by e end of June 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's fice at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the ecutive Engineer. The tenders should be accompanied by a statement in the form given ow, showing the rates at which the different items specified will be executed.